MYSORE DIVISION.

The 29th June 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore division, up to 15th July 1897, for restoring the Hondrabalu Tank, Registered No. 74, Chamrajnagar taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th May 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 (three hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Hondrabalu Tank, Registered No. 74 of Chamrajanagar taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items.	*Abstract of materials.*	*Per.*	*Quantity.*	*Rate.*
Bund—				
Earthwork	.. ..	C. yds.	22,591	
Old stone work	.. ..	,,	2,162	
New stone work	.. ..	,,	3,005	
Turfing ..	.. ..	S. yd.	11,051	
Jungle clearing	.. ..	L. S.	..	
Grade stone with opposite and bottom stones	.. ..	Each.	45	
Tank number stone	.. ..	,,	1	
Gauge stone	.. ..	,,	1	
Repairs to sluice and constructing waste weirs	.. ..	C. ft.	..	
Excavating foundation	.. .. ..	C. yds.	..	
Brick in surki mortar	.. .. ..	C. ft.	..	
Surki concrete	.. .. ..	,,	..	
Stone slab coping 6″ thick	.. .. ..	R. ft.	..	
New stone sujikat	.. ..	C. yds.	..	
Old stone do	.. .. ..	,,	..	

C. A. MAHADEVA SASTRI, *Executive Engineer.*

BANGALORE CITY MUNICIPALITY.

Proceedings of an Ordinary Meeting of the Municipal Commissioners for the City of Bangalore, held at their office premises at 7-30 A. M. on Thursday the 24th June 1897.

President.

Present—D. A. Choksi, Esq.

Ex-Officio Members.

Absent—The Sr. Surgeon & Sanitary Comr. with the Govt. of Mysore.
Do —The Principal, Central College.
Absent—The Superintendent, Central Jail.
Do —The Executive Engineer, Bangalore Dn.
Do —The Amildar of Bangalore taluk.

Municipal Commissioners.

I—Palace Division.

Absent—1. D. Devaraja Aras, Esq.
2. Vacant.

II—Balé Pettah Division.

Absent—1. B. Gangiah, Esq.
Present—2. D. Venkatramiah, Esq., B. A.

III—Manavarte Pettah Division.

Present—1. Veerabhadra Chetty, Esq.
Do —2. C. Krishna Murti, Esq.

IV—Alsur Pettah Division.

Absent—1. Boppannanavara Bassanna, Esq.
Present—2. Sher Khan Saib, Esq.

V—Nagarta Pettah Division.

Absent—1. Vairagi Setty Chikka Basanna, Esq.
Do —2. Sampannaiyana Dodda Muniyappa, Esq.

VI—Lal-Bagh Division.

Absent—1. J. Cameron, Esq.
Present—2. M. Rudrappa, Esq.

VII—Fort Division.